



140 Old Northport Road – Kings Park, NY 11754
Tel: (631) 368-4000
www.carlsoncorp.com

CarlsonCorp Inc

NYS DEC Permit No. 1-4734-00304/00005

RE: Acceptance Standards

CarlsonCorp Inc. is a NYS DEC permitted solid waste handler allowed to accept trees, brush, unadulterated wood, concrete, asphalt, rock, brick and soil, all uncontaminated (as defined in 360-16). Soil products entering the facility must fall under: **Lower level between Protection of Public Health-Residential Land Use and Protection of Groundwater Soil Cleanup Objectives in section 375-6.8(b)**. Materials in excess of the table will be reviewed on a case by case basis with the DEC to determine if CarlsonCorp Inc. can accept it as part of a beneficial use. Non-Brownfield sampling intervals must be at least 1 sample per 1000 CY with a sampling map included. Samples must contain a full NYS DEC 375.68(a) breakdown. Each sample must consist of a composite of at least 4 sample points and a grab for the VOC's. Brownfield sampling will be determined on a case by case basis by NYS DEC.

Upon arrival at CC, each load will be visually inspected to ensure that there is no presence of chemical odors, historic fill or comingled debris, including, but not limited to, wood, metal, tires and trash. It is expected that representatives of the Generator will inspect all materials prior to loading and leaving the project site so that unacceptable materials are not transported to CC. Failure to comply with the conditions of the visual inspection will result in rejection of the material at the entrance to the facility. All loads will be flagged and staged for a final DEC visual inspection. Upon DEC final visual inspection loads will be approved. Any materials misrepresented by the laboratory analytical data provided or unacceptable materials transported to CC are the responsibility of the Generator and will be disposed of at their cost, in accordance with the Generator Certification previously provided to you for execution by the appropriate project representative. This material acceptance is contingent upon the receipt of said executed Generator's Certification from the appropriate project representative.